

HOUSATONIC RIVER BASIN
DANBURY CONNECTICUT

PADANARAM RESERVOIR DAM CT 00067

PHASE I INSPECTION REPORT NATIONAL DAM INSPECTION PROGRAM



The original hardcopy version of this report
contains color photographs and/or drawings.
For additional information on this report
please email

U.S. Army Corps of Engineers
New England District
Email: Library@nae02.usace.army.mil

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

JULY 1980

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER CT 00067	2. GOVT ACCESSION NO. ADA142757	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Housatonic River Basin Danbury Conn., Padanaram Reservoir Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE July 1980
		13. NUMBER OF PAGES 50
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Housatonic River Basin Danbury Conn. Padanaram Reservoir Dam		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The Padanaram Reservoir is an earth embankment with a stone masonry faced downstream slope that is approx. 325 ft. long and 26.3 ft. high. The downstream stone face is on a 1:12 slope and the upstream earth embankment is on a 2.25:1 slope. The spillway is located at the southern abutment of the dam and is 24-foot long channel. There is a lower gate house in the center of the dam for the control of a discharge pipe that passes through the base of the dam. The size of the discharge pipe is unknown and the valve for its operation is inoperable. The drainage area is 3.7 square miles and the reservoir has 52 acre-feet of available storage.		

PADANARAM RESERVOIR DAM

CT 00067

HOUSATONIC RIVER BASIN

DANBURY, CONNECTICUT

PHASE I INSPECTION REPORT

NATIONAL DAM INSPECTION PROGRAM

NATIONAL DAM INSPECTION PROGRAM

PHASE I INSPECTION REPORT

Identification Number:	CT 00067
Name:	Padanaram Reservoir Dam
Town:	Danbury
County and State:	Fairfield County, Connecticut
Stream:	Padanaram Brook
Date of Inspection:	April 21, 1980

BRIEF ASSESSMENT


The Padanaram Reservoir Dam is an earth embankment with a stone masonry faced downstream slope that is approximately 325 feet long and 26.3 feet high. The downstream stone face is on a 1:12 slope and the upstream earth embankment is on a 2.25:1 slope. The spillway is located at the southern abutment of the dam and is 24-foot long channel. There is a lower gate house in the center of the dam for the control of a discharge pipe that passes through the base of the dam. The size of the discharge pipe is unknown and the valve for its operation is inoperable. The drainage area is 3.7 square miles and the reservoir has 52 acre-feet of available storage.


The assessment of the dam is based on the visual inspection, past operational performance and hydraulic/hydrologic computations. The dam is judged to be in fair condition with several areas that require attention. These areas include seepage through the dam and along the toe, vegetation on the stone face and along the toe of the dam and the nonoperating status of the blowoff.

The dam is classified as small and has a high hazard potential in accordance with guidelines established by the Corps of Engineers. The test flood for this dam is 1/2 the Probable Maximum Flood (PMF). The test flood inflow is 3,608 cfs and the routed test flood outflow is 3,460 cfs. The test flood outflow will overtop the dam by 2.3 feet.

It is recommended that the owner engage the services of a qualified registered engineer experienced in the design of dams to investigate the seepage through the dam and prepare a detailed hydraulic/hydrologic study to determine the spillway's adequacy.

Additional recommendations and remedial measures are included in Section 7 and should be implemented within one year after receipt of this Phase I Inspection Report.


Joseph F. Merluzzo
Connecticut P.E. #7639
Project Manager


Gary J. Giroux
Connecticut P.E. #11477
Project Engineer

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Inspections. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Inspection is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Inspection; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I Inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the Spillway Test Flood is based on the estimated Probable Maximum Flood for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and variety of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Inspection does not include an assessment of the need for fences, gates, "no trespassing" signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with Occupational Safety and Hazard Administration's (OSHA) rules and regulations is also excluded.

TABLE OF CONTENTS

	<u>Page</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface	i
Table of Contents	ii-iv
Overview Photo	
Location Map	

Section

1. PROJECT INFORMATION

1.1 General	1
a. Authority	1
b. Purpose of Inspection	1
1.2 Description of Project	1
a. Location	1
b. Description of Dam and Appurtenances	2
c. Size Classification	2
d. Hazard Classification	2
e. Ownership	3
f. Operator	3
g. Purpose of Dam	3
h. Design and Construction History	3
i. Normal Operational Procedure	3
1.3 Pertinent Data	3

2. ENGINEERING DATA

2.1 Design Data	7
2.2 Construction Data	7
2.3 Operation Data	7
2.4 Evaluation of Data	7

3. VISUAL INSPECTION

3.1 Findings	8
a. General	8
b. Dam	8
c. Appurtenant Structures	9
d. Reservoir Area	9
e. Downstream Channel	9

<u>Section</u>	<u>Page</u>
3.2 Evaluation	9
4. OPERATIONAL AND MAINTENANCE PROCEDURES	
4.1 Operational Procedures	10
a. General	10
b. Description of any Warning System in Effect	10
4.2 Maintenance Procedures	10
a. General	10
b. Operating Facilities	10
4.3 Evaluation	10
5. EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES	
5.1 General	11
5.2 Design Data	11
5.3 Experience Data	11
5.4 Test Flood Analysis	11
5.5 Dam Failure Analysis	12
6. EVALUATION OF STRUCTURAL STABILITY	
6.1 Visual Observations.	14
6.2 Design and Construction Data	14
6.3 Post-Construction Changes	14
6.4 Seismic Stability	14
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	
7.1 Dam Assessment	15
a. Condition	15
b. Adequacy of Information	15
c. Urgency	15
7.2 Recommendations	15


<u>Section</u>	<u>Page</u>
7.3 Remedial Measures	15
a. Operation and Maintenance Procedures . . .	15
7.4 Alternatives	16

APPENDICES

APPENDIX A - Inspection Checklist
APPENDIX B - Engineering Data
APPENDIX C - Photographs
APPENDIX D - Hydrologic and Hydraulic Computations
APPENDIX E - Information as Contained in the National Inventory of Dams




PADANARAM RESERVOIR DAM



QUADRANGLE: **DANBURY, CT**

US ARMY, CORPS OF ENGINEERS
NEW ENGLAND DIVISION
WALTHAM, MASS.



LOCATION MAP

PHASE I INSPECTION REPORT
PADANARAM RESERVOIR DAM CT 00067

SECTION 1 - PROJECT INFORMATION

1.1 General

a. Authority - Public Law 92-367, August 8, 1972 authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspections throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Storch Engineers has been retained by the New England Division to inspect and report on selected dams in the State of Connecticut. Authorization and notice to proceed were issued to Storch Engineers under a letter of March 6, 1980 from William E. Hodgson, Jr., Colonel, Corps of Engineers. Contract No. DACW33-80-C-0035 has been assigned by the Corps of Engineers for this work.

b. Purpose of Inspection -

(1) Perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) Encourage and prepare the states to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location - The Padanaram Reservoir Dam is located approximately 3 miles northwest of downtown Danbury and 3,700 feet north of the intersection of

Padanaram Road and Pembroke Road in the City of Danbury, Connecticut (See Location Map). The coordinates of the dam are approximately 41°-26' north latitude and 73°-29' west longitude. The dam is located on Padanaram Brook in the Housatonic River Basin.

b. Description of Dam and Appurtenances - The Padanaram Reservoir Dam is an earth embankment with a stone faced downstream slope that is 325 feet long and 26.3 feet high. The downstream stone face is on a 1:12 slope and the upstream earth embankment is on a 2.25:1 slope. The top of the dam is capped with concrete, 7 feet wide. The upstream embankment is lined with riprap.

The spillway is located through the southern abutment of the dam and consists of a 24-foot long stone weir and a 24-foot wide downstream spillway channel.

There is a lower gate house at the center of the dam with a valve that controls a discharge pipe that passes through the base of the dam. The size of the pipe is unknown. The valve in the gate house is not operable.

c. Size Classification - The Padanaram Reservoir Dam has a maximum height of 26.3 feet and a maximum storage of 132.5 acre-feet at the top of the dam. In accordance with the Recommended Guidelines for Safety Inspection of Dams established by the Corps of Engineers, the dam is classified as small (height less than 40 feet and storage less than 1,000 acre-feet).

d. Hazard Classification - The Padanaram Reservoir Dam is classified as having a high hazard potential. Failure of the dam could result in the loss of more than a few lives. Approximately 1,500 feet downstream are two homes which would be inundated by the flood wave. Estimated flow and water depths just prior to dam failure at this location is 600 cfs at 2 feet and just after dam failure is 12,000 cfs at 11 feet or an increase in depth of 9 feet.

e. Ownership - The Padanaram Reservoir Dam is owned by the City of Danbury, Connecticut.

f. Operator - The person in charge of day-to-day operation of the dam is:

Mr. John A. Schweitzer, Jr.
City Engineer
City of Danbury
Danbury, Connecticut 06810
(203) 797-4641

g. Purpose of Dam - The dam impounds the Padanaram Reservoir which serves as a water supply for the City of Danbury.

h. Design and Construction History - There are no design computations or construction drawings. The Padanaram Reservoir Dam was constructed in 1882.

i. Normal Operational Procedure - There are no operational procedures for the dam. Water impounded by the dam is used only in times of shortage.

1.3 Pertinent Data

a. Drainage Area - The Padanaram Reservoir drainage basin is in the City of Danbury and is irregular in shape. The area of the drainage basin is 3.7 square miles (Appendix D - Plate 3). Approximately 5 percent of the drainage basin is natural storage and more than 60 percent is developed. The topography is rolling with elevations ranging from 1,023 (NGVD) to 577 (NGVD) at the spillway crest. Approximately 45% of the watershed is controlled by East Lake Reservoir, another water supply reservoir.

b. Discharge at Damsite - There are no records available for discharge at the dam.

(1) Outlet works (conduit) size:	unknown
Invert elevation (feet above NGVD):	unknown
Discharge Capacity at top of dam:	unknown
(2) Maximum known flood at damsite:	unknown

(3)	Ungated spillway capacity at top of dam:	600 cfs
	Elevation (NGVD):	581.3
(4)	Ungated spillway capacity at test flood elevation:	1,050 cfs
	Elevation (NGVD):	583.6
(5)	Gated spillway capacity at normal pool elevation:	N/A
	Elevation (NGVD):	N/A
(6)	Gated spillway capacity at test flood elevation:	N/A
	Elevation:	N/A
(7)	Total spillway capacity at test flood elevation:	1,050 cfs
	Elevation (NGVD):	583.6
(8)	Total project discharge at top of dam:	600
	Elevation (NGVD):	581.3
(9)	Total project discharge at test flood elevation:	3,460 cfs
	Elevation (NGVD):	503.6
c.	Elevation (feet above NGVD)	
(1)	Streambed at toe of dam:	555
(2)	Bottom of cutoff:	unknown
(3)	Maximum tailwater:	560
(4)	Normal pool:	577
(5)	Full flood control pool:	N/A
(6)	Spillway crest (ungated):	577

	(7) Design surcharge (original design):	unknown
	(8) Top of dam:	581.3
	(9) Test flood surcharge:	583.6
d.	Reservoir (length in feet)	
	(1) Normal pool:	1,200
	(2) Flood control pool:	N/A
	(3) Spillway crest pool:	1,200
	(4) Top of dam:	1,250
	(5) Test flood pool:	1,300
e.	Storage (acre-feet)	
	(1) Normal pool:	80.5
	(2) Flood control pool:	N/A
	(3) Spillway crest pool:	80.5
	(4) Top of dam:	132.5
	(5) Test flood pool:	159.5
f.	Reservoir Surface (acres)	
	(1) Normal pool:	9.18
	(2) Flood control pool:	N/A
	(3) Spillway crest:	9.18
	(4) Test flood pool:	13.5
	(5) Top of dam:	12
g.	Dam	
	(1) Type:	earth embankment/stone masonry downstream face
	(2) Length:	325 feet
	(3) Height:	26.3 feet

- (4) Top width: 7 feet
- (5) Side slopes: U/S - 2.25:1
D/S - 1:12
- (6) Zoning: unknown
- (7) Impervious core: unknown
- (8) Cutoff: unknown
- (9) Grout curtain: unknown
- (10) Other: N/A
- h. Diversion and Regulating Tunnel N/A
- i. Spillway
- (1) Type: stone-broad crested
- (2) Length of weir: 24 feet
- (3) Crest elevation (without flashboard): 577
- (4) Gates: N/A
- (5) U/S channel: riprapped pond bottom
- (6) D/S channel: 24-foot riprapped and
natural channel
- (7) General: N/A
- j. Regulating Outlets
- (1) Invert elevation (NGVD): unknown
- (2) Size: unknown
- (3) Description: unknown
- (4) Control Mechanism manually operated gate
- (5) Other: gate not operable

SECTION 2 - ENGINEERING DATA

2.1 Design Data

There are no design computations or drawings available. The dam was designed by W. G. Worthington and D. G. Penfield, Engineers.

2.2 Construction Data

The dam was constructed in 1882 by George McKee, Contractors. There are no records or drawings available for the construction of the dam.

2.3 Operation Data

There are no operations at this dam. Water is pumped out during times of shortages. There is a discharge pipe but it is not operating.

2.4 Evaluation of Data

a. Availability - There were no computations or drawings available. There are no operating procedures.

b. Adequacy - The information made available along with the visual inspection, past performance history and hydraulic/hydrologic assumptions were adequate to assess the condition of the facility.

c. Validity - Due to the lack of available data, the conclusions and recommendations found in this report are based on the visual inspection and hydraulic/hydrologic computations.

SECTION 3 - VISUAL INSPECTION

3.1 Findings

a. General - The visual inspection was conducted on April 21, 1980 by members of the engineering staff of Storch Engineers, D. Baugh and Associates, Inc. and Matthews Associates with the help of Mr. Bruce Healy of the City of Danbury, Connecticut. A copy of the visual inspection check list is contained in Appendix A of this report. Selected photos of the dam and appurtenant structures are contained in Appendix C.

In general, the overall appearance and condition of the facility and its appurtenant structures is fair.

b. Dam - The dam is an earth embankment with a stone masonry faced downstream slope. The downstream face of the dam needs repointing in areas where vegetation has been growing from the joints (Photo 1). There appears to be a bulge in the masonry just to the east of the gate house. A closer look at this bulge, however, does not show any distress in the mortared joints. The alignment of the top of the dam is good (Photo 2) and no bulges are apparent. The upstream embankment is brush covered and there are areas where the riprap has moved (Photo 2). The top of the dam is level with no signs of settlement. The stone wingwall is in good condition.

Just below the toe of the dam and to the east of the gate house, there is a steady seepage flow (Photos 7 and 8) which was estimated to be approximately 50 to 75 gallons per minute. This seepage is clear and does not show any signs of particle movement. The estimated quantity of flow is from the entire area as shown on the Photo Location Plan.

c. Appurtenant Structures - The lower gate house (Photo 6) is structurally sound, however, the valve is not operating and the type and size of the discharge pipe is unknown. The discharge pipe outlets approximately 50 feet downstream and is silted-up and has not experienced flow in years.

The spillway is a stone weir that is in fair condition (Photo 3). The approach channel is not well defined and is the natural slope of the bottom of the pond. The training walls of the spillway are also stone masonry and are in fair condition. The downstream channel is a natural channel with riprap in some areas. It is 24 feet wide with steep side slopes (Photo 4). The condition is good except for areas of the channel where debris is cluttered.

d. Reservoir Area - The area immediately adjacent to the facility is steeply sloped and in a natural state. The shoreline shows no signs of sloughing or erosion and there is no development adjacent to the reservoir. A rapid rise in the water level of the reservoir will not endanger any life or property.

e. Downstream Channel - The downstream channel is a natural channel lined with rock and rock outcroppings.

3.2 Evaluation

Overall, the general condition of the dam is fair. The visual inspection revealed items that lead to this assessment, and apparent areas of distress such as:

- a. Seepage from the toe.
- b. Inoperation of the blowoff.
- c. Vegetation on the downstream face along the toe of the dam and the downstream channel.

SECTION 4 - OPERATIONAL AND MAINTENANCE PROCEDURES

4.1 Operational Procedures

a. General - The operation of this facility is for water supply purposes and the reservoir is kept as full as possible. The discharge pipe through the dam cannot be controlled because the valve is frozen shut and is inoperable.

b. Description of any Warning System in Effect - There is no warning system in effect for this dam.

4.2 Maintenance Procedures

a. General - This dam is minimumly maintained.

b. Operating Facilities - Valve to the discharge pipe is not operable.

4.3 Evaluation

The maintenance of the dam is less than adequate in that proper care of the dam embankment should be on a regular basis. The valve to the discharge pipe should be maintained in working order and there should be a proper operating procedure and warning system in effect.

SECTION 5 - EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES

5.1 General

The Padanaram Reservoir Dam is an earth embankment with a stone masonry faced downstream slope approximately 325 feet long and 26.3 feet high. The spillway is a stone weir, 24 feet long. The downstream channel is 24 feet wide and is natural ground with some riprap. A discharge pipe passes through the base of the dam. The size of the pipe is not known and the valve is inoperable.

The watershed encompasses 3.7 square miles and is more than 60 percent developed. The topography is rolling with the terrain rising 446 feet from the spillway crest.

The pond has a total capacity of 132.5 acre-feet when the pond is at the top of the dam and 80.5 acre-feet at the spillway crest. Therefore, there is approximately 32 acre-feet of storage available. The test flood outflow for this dam is 3,460 cfs and the spillway capacity is 600 cfs or approximately 17% of the test flood outflow.

5.2 Design Data

No design data is available.

5.3 Experience Data

The Padanaram Reservoir Dam has experienced all the major storms of the 1930's and 1950's and most recently January, 1979. The flood of record in the Danbury area resulted from the storm of October, 1955.

5.4 Test Flood Analysis

Based on the guidelines found in the Recommended Guidelines for Safety Inspection of Dams, the dam is classified as small structure with a high hazard

potential. The test flood for these conditions ranges from 1/2 the Probable Maximum Flood (PMF) to the PMF. One half the PMF was used for this dam because of its size.

Using the guide curves established by the Corps of Engineers (rolling terrain), the test flood inflow is 3,608 cfs. The routing procedure established by the Corps gives an approximate outflow of 3,460 cfs. The spillway capacity is approximately 600 cfs or approximately 17% of the test flood outflow. The test flood will overtop the dam by approximately 2.3 feet.

In the development of the test flood inflow, it was assumed that the East Lake Reservoir Dam had no effect on the peak inflow. Although it does, the actual amount is negligible. This simplified the development of the inflow hydrograph, the routing through the dam and the outflow hydrograph for Padanaram Reservoir Dam.

Storage behind the dam was assumed to begin at the elevation of the spillway crest. Storage was determined by an average area depth analysis. Capacity curves for the spillway assumed weir flow.

5.5 Dam Failure Analysis

A dam failure analysis was performed using the Rule of Thumb method in accordance with guidelines established by the Corps of Engineers. Failure was assumed to occur when the water level in the reservoir was at the top of the dam.

The spillway discharge just prior to dam failure is 600 cfs and will produce a depth of flow of approximately 2 feet several hundred feet downstream from the dam. The calculated dam failure discharge is 19,050 cfs and will produce a depth of flow of approximately 10 feet several hundred feet downstream from the dam or an increase in water depth at failure of approximately 8 feet. The failure

analysis covered a distance of approximately 4,700 feet downstream where the depth of flow was calculated to be 4.5 feet or an increase of approximately 2.5 feet.

Failure of the Padanaram Reservoir Dam may result in the loss of more than a few lives and may damage at least two dwellings located approximately 1,500 feet downstream. Flow due to failure at this location will be approximately 12,000 cfs at a depth of 11 feet.

SECTION 6 - EVALUATION OF STRUCTURAL STABILITY

6.1 Visual Observations

The general structural stability of the dam is good as evidenced by the vertical, horizontal and lateral alignment of the face and top of the dam and by the age of the dam. A bulge was noted on the front face of the dam east of the centerline, extending about 1/4 of the length. This bulge, however, appears to have originated during construction because no cracking of the masonry or mortar was observed. Some joints in the masonry need repointing as evidenced by the vegetative growth from the joints.

The spillway channel is in fair condition. It should be cleared of the accumulated debris and some of the stones realigned.

Some possible problem areas are seepage at the toe of the dam and the cluttered spillway.

6.2 Design and Construction Data

No design data or construction drawings are available.

6.3 Post-Construction Changes

No information on post-construction changes are available.

6.4 Seismic Stability

The dam is located in Seismic Zone 1 and in accordance with Recommended Phase I Guidelines does not warrant a seismic analysis.

SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition - After consideration of the available information, the results of the inspection and hydraulic/hydrologic computations, the general condition of the Padanaram Reservoir Dam is fair.

b. Adequacy of Information - The information available is such that an assessment of the safety of the dam should be based on available data, the visual inspection results, past operational performance of the dam and its appurtenant structures and computations developed for this report.

c. Urgency - It is considered that the recommendations suggested below be implemented within one year after receipt of this Phase I Inspection Report.

7.2 Recommendations

The following recommendations should be carried out under the direction of a qualified registered engineer.

- a. Seepage through the dam and at the toe of the dam should be investigated further to determine its origin and monitored to determine any changes.
- b. Prepare a detailed hydraulic/hydrologic study to determine spillway adequacy and an increase of the total project discharge if necessary.
- c. Trees including stumps and root systems should be removed from the toe and embankment slopes and backfilled with proper material.

7.3 Remedial Measures

- a. Operation and Maintenance Procedures -

(1) Spillway channel should be cleared of debris and relined with the stone available.

(2) Vegetation on the downstream face of the dam and trees along the toe of the dam should be removed. This will facilitate the visual observation of existing and potential seepage.

(3) Discharge valve and pipe should be repaired. Valve for the discharge pipe should be on the upstream side of the embankment.

(4) Plans for a regular program of operation and maintenance of the dam should be initiated.

(5) Plans for around-the-clock surveillance should be developed for periods of unusually heavy rains and a formal downstream warning system should be put into operation for use in the event of an emergency.

(6) A program of annual technical inspection should be established.

7.4 Alternatives

None.

APPENDIX A

INSPECTION CHECK LIST

INSPECTION CHECK LIST

PARTY ORGANIZATION

PROJECT PADANARAM RESERVOIR DAM

DATE 4/21/80

TIME 11:00 a.m.

WEATHER Clear

W.S. ELEV. _____ U.S. _____ DN.S. _____

PARTY:

- | | |
|---|-----------------------------------|
| 1. <u>John F. Schearer, SE Civil</u> | 6. <u>Peter Austin, DBA Civil</u> |
| 2. <u>John Pozzato, MA Mech.</u> | 7. <u>Bruce Healy, Danbury</u> |
| 3. <u>Kenneth J. Pudeler, SE Civil</u> | 8. _____ |
| 4. <u>Gary J. Giroux, SE Hyd/Civil</u> | 9. _____ |
| 5. <u>Michael Haire, SE Struct/Geo.</u> | 10. _____ |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. _____		
2. _____		
3. _____		
4. _____		
5. _____		
6. _____		
7. _____		
8. _____		
9. _____		
10. _____		

INSPECTION CHECK LIST

PROJECT PADANARAM RESERVOIR DAM DATE 4/21/80
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITIONS
<u>DAM EMBANKMENT</u>	
Crest Elevation	Good
Current Pool Elevation	Fair to good/some erosion
Maximum Impoundment to Date	No information available
Surface Cracks	Minor
Pavement Condition	Good
Movement or Settlement of Crest	None
Lateral Movement	None
Vertical Alignment	Good
Horizontal Alignment	Good
Condition at Abutment and at Concrete Structures	Good
Indications of Movement of Structural Items on Slopes	N/A
Trespassing on Slopes	Problem
Vegetation on Slopes	Some through joints - minor
Sloughing or Erosion of Slopes or Abutments	Upstream - some/minor
Rock Slope Protection - Riprap Failures	Minor upstream
Unusual Movement or Cracking at or near Toes	None
Unusual Embankment or Downstream Seepage	Negligable through dam - some below dam.
Piping or Boils	None
Foundation Drainage Features	None
Toe Drains	None
Instrumentation System	None

INSPECTION CHECK LIST

PROJECT PADANARAM RESERVOIR DAM

DATE 4/21/80

PROJECT FEATURE _____

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED

CONDITION

CUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE

Underwater

a. Approach Channel

Slope Conditions

Bottom Conditions

Rock Slides or Falls

Log Boom

Debris

Condition of Concrete Lining

Drains or Weep Holes

b. Intake Structure

Condition of Concrete

Stop Logs and Slots

INSPECTION CHECK LIST

PROJECT PADANARAM RESERVOIR DAM

DATE 4/21/80

PROJECT FEATURE _____

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - CONTROL TOWER</u>	
a. Concrete and Structural Stone masonry	
General Condition	Fair
Condition of Joints	Fair
Spalling	N/A
Visible Reinforcing	N/A
Rusting or Staining of Concrete	N/A
Any Seepage or Efflorescence	Minor
Joint Alignment	N/A
Unusual Seepage or Leaks in Gate Chamber	N/A
Cracks	N/A
Rusting or Corrosion of Steel	N/A
b. Mechanical and Electrical	
Air Vents	None
Float Wells	None
Crane Hoist	None
Elevator	None
Hydraulic System	None
Service Gates	None
Emergency Gates	None
Lightning Protection System	None
Emergency Power System	None
Wiring and Lighting System in Gate Chamber	None

INSPECTION CHECK LISTPROJECT PADANARAM RESERVOIR DAMDATE 4/21/80

PROJECT FEATURE _____

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED**CONDITION****OUTLET WORKS - TRANSITION AND CONDUIT**

Inaccessible

General Condition of Concrete

Rust or Staining on Concrete

Spalling

Erosion or Cavitation

Cracking

Alignment of Monoliths

Alignment of Joints

Numbering of Monoliths

INSPECTION CHECK LIST

PROJECT PADANARAM RESERVOIR DAM

DATE 4/21/80

PROJECT FEATURE _____

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED

CONDITION

OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL

General Condition of Concrete

N/A

Rust or Staining

N/A

Spalling

N/A

Erosion or Cavitation

N/A

Visible Reinforcing

N/A

Any Seepage or Efflorescence

N/A

Condition at Joints

N/A

Drain holes

N/A

Channel

Not well defined

Loose Rock or Trees Overhanging
Channel

Brush and trees in channel

Condition of Discharge Channel

Fair

INSPECTION CHECK LIST

PROJECT PADANARAM RESERVOIR DAM

DATE 4/21/80

PROJECT FEATURE _____

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	Underwater
General Condition	
Loose Rock Overhanging Channel	
Trees Overhanging Channel	
Floor of Approach Channel	
b. Weir and Training Walls	Dry rubble
General Condition of Concrete	Fair
Rust or Staining	N/A
Spalling	N/A
Any Visible Reinforcing	N/A
Any Seepage or Efflorescence	N/A
Drain Holes	N/A
c. Discharge Channel	
General Condition	Fair
Loose Rock Overhanging Channel	Some
Trees Overhanging Channel	Some
Floor of Channel	Natural rock - good
Other Obstructions	None

INSPECTION CHECK LIST

PROJECT PADANARAM RESERVOIR DAM

DATE 4/21/80

PROJECT FEATURE _____

NAME _____

DISCIPLINE _____


NAME _____

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - SERVICE BRIDGE</u></p> <p>a. Super Structure</p> <p>Bearings</p> <p>Anchor Bolts</p> <p>Bridge Seat</p> <p>Longitudinal Members</p> <p>Under Side of Deck</p> <p>Secondary Bracing</p> <p>Deck</p> <p>Drainage System</p> <p>Railings</p> <p>Expansion Joints</p> <p>Paint</p> <p>b. Abutment & Piers</p> <p>General Condition of Concrete</p> <p>Alignment of Abutment</p> <p>Approach to Bridge</p> <p>Condition of Seat & Backwall</p>	<p>N/A</p>


APPENDIX B

ENGINEERING DATA

PADANARAM RESERVOIR



Outlet
PLAN



ELEVATION

SECTION A A



NOT TO SCALE

PLATE 1

STORCH ENGINEERS WETHERSFIELD,CONNECTICUT		U.S.ARMY ENGINEER DIV. NEW ENGLAND CORPS. OF ENGINEERS WALTHAM MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED.DAMS			
PADANARAM RESERVOIR DAM			
			SCALE: AS SHOWN ,
			DATE JULY 1980

APPENDIX C

PHOTOGRAPHS



PLAN

PHOTO LOCATION PLAN

PLATE 2

STORCH ENGINEERS
WETHERSFIELD, CONNECTICUT

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

PADANARAM RESERVOIR DAM

NOT TO SCALE

SCALE: AS SHOWN
DATE JULY 1980

C-1



PHOTO 2
CREST OF DAM



PHOTO 1
DOWNSTREAM FACE OF DAM



PHOTO 3
SPILLWAY-UPSTREAM



PHOTO 4
SPILLWAY CHANNEL-DOWNSTREAM



PHOTO 5
VIEW LOOKING DOWNSTREAM



PHOTO 6
LOWER GATE HOUSE & OUTLET

C-III



PHOTO 7
SEEPAGE NEAR TOE OF DAM



PHOTO 8
SEEPAGE NEAR TOE OF DAM

APPENDIX D

HYDROLOGIC AND HYDRAULIC COMPUTATIONS

STORCH ENGINEERS
Engineers - Landscape Architects
Planners - Environmental Consultants

JOB Phase I Dam Inspection - #4463

SHEET NO. 1

OF 10

CALCULATED BY P. A.

DATE 4/25/80

CHECKED BY RDC

DATE 7/15/80

Determination of PMF

NAME OF DAM PADANARAM RES. DAM

DRAINAGE AREA 3.7 SQ MI

INFLOW 975 CFS / SQ MI

$$V_2 \text{ PMF} = (975 \text{ CFS/SQ MI})(3.7 \text{ SQ MI}) = 3608 \text{ CFS}$$

$$Q_{100} = 340 \times A^{.79} = 956 \text{ CFS}$$

Estimating the effect of surcharge storage on the Maximum Probable Discharges

1. $Q_{p1} = \underline{3608} \text{ cfs}$

2a. $H_1 = \underline{6.65'} \text{ (elev.)}$

b. $\text{STOR}_1 = \underline{0.4''}$

c. $Q_{p2} = Q_{p1} (1 - \text{STOR}_1 / 0.3) = \underline{3460} \text{ cfs}$

3a. $H_2 = \underline{6.60}$

$\text{STOR}_2 = \underline{0.4''}$

b. $\text{STOR}_A = \underline{0.4''}$

$Q_{PA} = \underline{3460} \text{ CFS}$

$H_A = \underline{6.6}$

$\text{STOR}_A = \underline{0.4''}$

PMF = 3460 cfs

100 YR.

956 CFS

4.97'

0.3''

900 CFS

4.90'; 0.3''

0.3

900 CFS

4.9'; 0.3''

900 CFS

Capacity of the spillway when the pond elevation is at the top of the dam

$Q = \underline{600} \text{ cfs or } \underline{17} \% \text{ of the } \text{PMF}$

6.7 % OF 100 YR

STORCH ENGINEERS
Engineers - Landscape Architects
Planners - Environmental Consultants

JOB Phase I Dam Inspection 4463

SHEET NO. 2 OF 10

CALCULATED BY GJG DATE 4/16/80


CHECKED BY BDC DATE 7/15/80

AREA - CAPACITY

Name of Dam: PADANARAM RES. DAM

ELEV	DEPTH	AREA	AVG. AREA	VOL	Σ VOL
0		9.18			0
3.0	3.0	11.9	10.5	31.5	31.5
13.0	10.0	15.6	13.5	135.0	166.5

Elev (ft) Storage below spillway is approximately 80.5 Acre-ft



Capacity (Acre-ft)

STORCH ENGINEERS
Engineers - Landscape Architects
Planners - Environmental Consultants

JOB Phase I Dam Inspection 4463


SHEET NO. 3 OF 10

CALCULATED BY P.A. DATE 4/25/80

CHECKED BY BDC DATE 7/15/80

SCALE Stage Discharge

NAME OF DAM <u>PADANARAM RES. DAM</u>													
$Q = CLH^{3/2}$													
Spillway I					Spillway II				Dam				QT
Elev	C	L	H	Q	C	L	H	Q	C	L	H	Q	
	2.70	24	0.5	23									23
	2.63	24	1.0	63									63
	2.63	24	1.5	116									116
	2.63	24	2.0	179									179
	2.63	24	2.5	250									250
	2.63	24	3.0	328									328
	2.63	24	3.5	413									413
	2.63	24	4.0	505									505
	2.63	24	4.5	603									603
	2.63	24	5.0	706					2.65	300	0.5	281	987
	2.63	24	5.5	814					2.65	300	1.0	795	1609
	2.63	24	6.0	928					2.65	300	1.5	1461	2389
	2.63	24	6.5	1046					2.65	300	2.0	2249	3296
	2.63	24	7.0	1169					2.65	300	2.5	3143	4312



Downstream Hydrographs

"Rule of Thumb" Guidance for Estimating Downstream Failure Hydrographs

NAME OF DAM PADANARAM RES. DAM

Section I at Dam

1. $S_1 = \frac{132}{8/27 W_b \sqrt{g}} \text{ Acft}$
2. $Q_{p1} = \left(\frac{8}{27} \times 84' \right) \sqrt{32.2 \text{ sec}^2} (26.3)^{3/2} = 19050 \text{ cfs}$
3. See Sections

Section II at

- a. $H_2 = 11.4'$ $A_2 = 1150$ $L_2 = 800$ $V_2 = 21.1 \text{ Acft}$
- b. $Q_{p2} = Q_{p1} (1 - V_2/S_1) = 16,000 \text{ cfs}$
- c. $H_2 = 10.5'$ $A_2 = 1000 \text{ SF}$
 $A_A = 1075 \text{ SF}$ $V_2 = 19.7 \text{ Acft}$
 $Q_{p2} = 19050 (1 - 19.7/132) = 16200 \text{ cfs}$

Section III at

- a. $H_3 = 12.5'$ $A_3 = 1350 \text{ SF}$ $L_3 = 1000'$ $V_3 = 30.9 \text{ Acft}$
- b. $Q_{p3} = Q_{p2} (1 - V_3/S_2) = 11740 \text{ cfs}$
- c. $H_3 = 11.0'$ $A_3 = 1080 \text{ SF}$
 $A_A = 7215 \text{ SF}$ $V_3 = 27.9 \text{ Acft}$
 $Q_{p3} = 16200 (1 - 27.9/112.3) = 12175 \text{ cfs}$

Section IV at

- a. $H_4 = 12.2'$ $A_4 = 1500 \text{ SF}$ $L_4 = 1000'$ $V_4 = 34.4 \text{ Acft}$
- b. $Q_{p4} = Q_{p3} (1 - V_4/S_3) = 7210 \text{ cfs}$
- c. $H_4 = 9.7'$ $A_4 = 1000 \text{ SF}$
 $A_A = 1250 \text{ SF}$ $V_4 = 28.7 \text{ Acft}$
 $Q_{p4} = 12175 (1 - 28.7/84.4) = 8035 \text{ cfs}$

STORCH ENGINEERS
Engineers - Landscape Architects
Planners - Environmental Consultants

JOB Phase I Dam Inspection - #4463

SHEET NO. 5 OF 10

CALCULATED BY P.A. DATE 4/28/80

CHECKED BY BDC DATE 7/15/80

Downstream Hydrographs (Continued)

Section V at

4a. $H_5 = 10.2'$ $A_5 = 1720 \text{ SF}$ $L_5 = 7100'$ $V_5 = 28.3 \text{ Acft}$

b. $Q_{p5} = Q_{p4} (1 - V_5/S) = 3952 \text{ cfs}$

c. $H_5 = 7.2'$ $A_5 = 600 \text{ SF}$
 $A_A = 860 \text{ SF}$ $V_5 = 21.7 \text{ Acft}$

$Q_{p5} = 8035 (1 - 21.7/55.7) = 4900 \text{ cfs}$

Section VI at

4a. $H_6 = 7.0'$ $A_6 = 900 \text{ SF}$ $L_6 = 750'$ $V_6 = 15.5 \text{ Acft}$

b. $Q_{p6} = Q_{p5} (1 - V_6/S) = 2660 \text{ cfs}$

c. $H_6 = 4.5'$ $A_6 = 500 \text{ SF}$
 $A_A = 700 \text{ SF}$ $V_6 = 12.0 \text{ Acft}$

$Q_{p6} = 4900 (1 - 12/34) = 3170 \text{ cfs}$

Section VII at

4a. $H_7 = 5.5'$ $A_7 =$ $L_7 =$ $V_7 =$ Acft


b. $Q_{p7} = Q_{p6} (1 - V_7/S) =$ cfs

c. $H_7 =$ $A_7 =$
 $A_A =$ $V_7 =$ Acft


$Q_{p7} =$

STORCH ENGINEERS/STORCH ASSOCIATES
Engineers - Landscape Architects
Planners - Environmental Consultants

JOB 4463
 SHEET NO. 6 OF 10
 CALCULATED BY BAH DATE 5/30/80
 CHECKED BY BDC DATE 7/15/80
 SCALE Section II



D	WP	A	R	R^2	$S^{\frac{1}{2}}$	V	Q
2	40	70	1.75	1.45	0.16	6.90	483
5	85	288	3.39	2.27		10.79	3108
8	120	600	5.00	2.94		13.98	8388
10	150	900	6.00	3.32		15.79	14211
20	265	2950	11.13	5.03		23.92	70569
30	390	6300	16.15	6.45	0.16	30.67	193221



STORCH ENGINEERS/STORCH ASSOCIATES

Engineers - Landscape Architects
Planners - Environmental Consultants


JOB 4463

SHEET NO. 7 OF 10

CALCULATED BY BAH DATE 5/30/80

CHECKED BY BAC DATE 7/15/80

SCALE Section III



$n = .05$
 $S = 1.10\%$

D	W	A	R	R^2	$S^{1/2}$	V	Q
2	50	75	1.5	1.3	.105	4.1	307
5	85	275	3.2	2.2	.105	6.8	1890
8	125	600	4.8	2.86	.105	8.9	5370
10	155	900	5.8	3.2	.105	10.1	9150
20	280	3050	10.8	4.95	.105	15.4	47270
30	400	6375	15.9	6.4	.105	19.9	127500

Depth (ft)

20
18
16
14
12
10
8
6
4
2
0

Area

Capacity

Discharge

Area

3000
30000

STORCH ENGINEERS/STORCH ASSOCIATES

Engineers - Landscape Architects
Planners - Environmental Consultants

JOB

41-163

SHEET NO.

8

OF

10

CALCULATED BY

BAH

DATE

5/30/80

CHECKED BY


BDC

DATE


7/15/80

SCALE

Section IV & V




D	W	A	R	R ³	S ^{1/2}	V	Q
2	70	120	1.71	1.4	.07	3.0	360
5	100	375	3.75	2.4	.07	5.1	1910
8	130	720	5.5	3.1	.07	6.65	4790
10	160	1050	6.6	3.5	.07	7.44	7820
20	260	3100	11.9	5.2	.07	11.1	34,125
30	370	6300	17.0	6.68	.07	14.1	89,000




STORCH ENGINEERS/STORCH ASSOCIATES
Engineers - Landscape Architects
Planners - Environmental Consultants

JOB 4463
 SHEET NO. 9 OF 10
 CALCULATED BY BAH DATE 5/30/80
 CHECKED BY BDC DATE 7/5/80
 SCALE Section VI



$n = .05$
 $S = 0.45\%$

D	W	A	R	R^2	$S^{1/2}$	V	Q
2	85	135	1.59	1.36	.067	2.71	366
5	160	525	3.28	2.20	.067	4.38	2300
8	230	1120	4.87	2.87	.067	5.71	6400
10	280	1650	5.89	3.26	.067	6.49	10711
20	510	5600	10.98	4.94	.067	9.84	55086
30	750	12000	16	6.35	.067	12.64	151732



APPENDIX E

INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS